



5000 PSI CONCRETE @ 28 DAYS
 MANUFACTURED TO MEET OR EXCEED ASTM SPEC C-478.
 H2O LOADING
 OPENINGS CAST AT REQUIRED LOCATIONS

MBO PRECAST, INC.

4 MARION DR. CARVER MA. 02330

PH: 508-866-6900 FAX: 508-866-5252



www.mboprecast.com



Show Name
4' DIA DRAIN MANHOLE

Reference

Drawn By

Date

CMH

9-2011

CAD File Name