



4000 PSI CONCRETE @ 28 DAYS
 REINFORCING GRADE 60 # 3 BAR
 WEIGHT = 6300 LBS

MBO PRECAST, INC.

4 MARION DR. CARVER MA. 02330

PH: 508-866-6900 FAX: 508-866-5252



www.mboprecast.com



Show Name

WINGWALL FOR 12" PIPE

Reference

Drawn By

CMH

Date

10-2001

CAD File Name